


# The Berkshire Golf Club

Ascot



## Case Study

**Client:** The Berkshire Golf Club

**Architect:** Sutton Griffin Architects

**Quantity Surveyor:** Henry Riley LLP

**Duration:** 21 weeks

**Value:** £403k

### Club House Re-Roofing

This project comprised the following works carried out within a live environment:

- Removing of existing tiled roof finish to the Club House, including Tiles, Tiling battens, Bituminous felt.
- Removal of flat roof coverings
- Removing of existing guttering and down pipes
- Installation of new tiled roof including all tiles, ridges, valleys, Hips, battens, breathable felt; vapour control.
- Installation of new aluminium gutters and down pipes.
- Installation of new PVC over cladding to dormas.
- Inclusion of Bat access tiles and works as per Ecologist report

